

Sertifikat Certificate



INSTITUT
"MIHAJLO PUPIN"
CENTAR ZA
GASNU TEHNIKU
Volgina 15,
BEOGRAD SRBIJA
tel: +381 11 6772 151
fax: +381 11 6781-02
impccgt@pupin.rs

SERTIFIKAT

☒ O PREGLEDU TIPa / Type examination

Broj / Number: T 1919

☐ POJEDINAČNI PREGLED / Single examination

Strana / Page: 1 / 2

Na zahtev naručioca /
By the request of purchaser:

Fondital S.p.A, Via Cerreto 40, 25079 Vobarno (BS),
Italija / Italy

preduzeto je/
has been undertaken:

Kontrolisanje novog proizvoda
the new product inspection

u vezi sa Izveštajem o usaglašenosti/
in relation to Inspection report:

Broj /
Number: T 1919

sa dokumentima u prilogu/
with attached documents:

- Uputstvo za korišćenje / User's manual
- Uputstvo za instaliranje / Installation instruction;
- Dokumentacija o proizvodu / Product documentation;
- Izveštaji o ispitivanju GP18-0023035-01-RP01 i GP18-0023035-02-RP01 / Test reports GP18-0023035-01-RP01 i GP18-0023035-02-RP01

INSTITUT "MIHAJLO PUPIN" - CENTAR ZA GASNU TEHNIKU izjavljuje da:
INSTITUTE "MIHAJLO PUPIN" - GAS TECHNIQUE CENTRE declares that:

predmet ocenjivanja /
subject of the inspection:

GASNI KONDENZACIONI KOTAO /
GAS CONDENSATION BOILER

proizveden od /
manufactured by:

Fondital S.p.A, Via Cerreto 40, 25079 Vobarno (BS),
Italija / Italy

oznaka - tip - serija /
mark - type - series:

Fondital ANTEA KC/KR/KRB ...
Nova Florida DELFIS KC/KR/KRB ...

vrsta/type: B₂₃, C₁₃, C₃₃
kategorija/category: II_{2H3P}

kako je specificirano u Prilogu
A, zadovoljava zahteve
navedene u /
as specified in the Annex A, meets
the requirements listed in:

Pravilnik o zahtevima za projektovanje, izradu i
ocenjivanje usaglašenosti gasnih aparata ("Sl. gl.
RS", br. 41/2015)

SRPS EN 15502-2-1:2013

Sertifikat o kontrolisanju se izdaje na osnovu standarda SRPS ISO/IEC 17020:2012 i
Rešenja Ministarstva rudarstva i energetike br. 312-01-01508/2016-05 /

The inspection certificate is issued on the basis of standard SRPS ISO/IEC 17020:2012
and the decree of the Ministry of Mining and Energy N° 312-01-01508/2016-05.

Ocenjivanje sprovedeno / Evaluation performed from: 11.07.2019. - 16. 09. 2019.

izdat od / issued by:

INSTITUT MIHAJLO PUPIN
CENTAR ZA GASNU TEHNIKU/
INSTITUTE MIHAJLO PUPIN
GAS TECHNIQUE CENTRE

mesto, datum / place, date:


Beograd, 16.09.2019.

M.P. /

S.P. BELGRADE

Kristina Petković dipl.maš.inž.

Ime, Prezime / Name, Surname



Sertifikat Certificate



INSTITUT
"MIHAJLO PUPIN"
CENTAR ZA
GASNU TEHNIKU
Volgina 15,
BEOGRAD SRBIJA
tel: +381 11 6772 151
fax: +381 11 6781-02
impcgt@pupin.rs

Prilog A / Annex A

Broj / Number: T 1919

Strana / Page: 2 / 2

oznaka - tip - serija /
mark - type - series :

Fondital ANTEA KC/KR/KRB ...
Nova Florida DELFIS KC/KR/KRB ...

vrsta/type: B₂₃, C₁₃, C₃₃
kategorija/category: II_{2H3P}

detaljno oznaka - tip - serija / mark - type - series specification :	tehničke karakteristike / technical characteristics :	kratak opis / short description :
Fondital ANTEA ... Nova Florida DELFIS ...		
...KC/KR/KRB 12	$Q_n = 2,0 \div 12,0 \text{ kW}$ $P_n = 1,8 \div 11,7 \text{ kW}$ $P_n = 2,1 \div 12,6 \text{ kW}^*$	KR - samo centralno grejanje / <i>only central heating</i> ;
...KC/KR/KRB 24	$Q_n = 3,0 \div 23,7 \text{ kW}$ $P_n = 2,8 \div 22,8 \text{ kW}$ $P_n = 3,2 \div 24,9 \text{ kW}^*$	KC - centralno grejanje i trenutnu toplu sanitarnu vodu / <i>central heating and instantaneous hot water</i>
...KC/KR/KRB 28	$Q_n = 3,3 \div 26,4 \text{ kW}$ $P_n = 3,1 \div 25,5 \text{ kW}$ $P_n = 3,5 \div 28,0 \text{ kW}^*$	KRB - centralno grejanje i priključenje na spoljni grejač sanitarne vode / <i>central heating and external hot water heater</i>

* Napomen / Note : **Za** / For (50/30) °C

Bilo kakve promene na uređaju moraju se prijaviti izdavaocu ove isprave. /
Any changes on the device must be reported to the issuer of this document

Definisani rok narednog pregleda je godinu dana u sklopu ocenjivanja
Deklaracija usaglašenosti sa tipom! / The deadline for the next review is one
year within the assessment of the Declaration of Conformity with the type!

Poslednja nadzorna poseta obavljena 14.06.2021. /
The last audit was done 14.06.2021.